



transport

Department:
Transport
Province of KwaZulu-Natal

PROVINCE OF KWAZULU-NATAL DEPARTMENT OF TRANSPORT

TRANSPORT INFRASTRUCTURE AND REGIONAL SERVICES

UNDERBERG REGION

**UPGRADE OF MAIN ROAD P419
FROM KM 4.4 – KM 9.4 & KM 17.0 – KM 22.0**

PAVEMENT DESIGN REPORT

DATE: JULY 2020

<p>Issued to: The Department of Transport 172 Burger Street PIETERMARITZBURG 3201</p> <p>Contact Name: Mr Zwakala Zuma Telephone:</p>	<p>Prepared by: Ilifa Africa Engineers (Pty) Ltd 35A Piet Retief Street HARRISMITH 9880</p> <p>Contact Name: Mr. J. van Wyk Telephone: (058) 622 1297</p> 
---	---



DOCUMENT CONTROL SHEET

TITLE: PAVEMENT DESIGN REPORT		THE UPGRADING OF MAIN ROAD P419 FROM KM 4.4 TO KM 9.4 AND KM 17 to KM 22		
ILIFA PROJECT NO: H19-001-00	DATE: 2020-07-21	REPORT STATUS: DRAFT		
CARRIED OUT BY:		COMMISSIONED BY:		
Ilifa Africa Engineers (Pty) Ltd P O Box 802 HARRISMITH 9880 Tel: +27 (58) 622 1211 Fax: +27 (58) 623 0827 E-mail: harrismith@ilifa.biz		The Department of Transport 172 Burger Street PIETERMARITZBURG 3201 Tel: +27 (33) 355 0573 Fax: +27 (33) 355 8772		
AUTHOR: Mr. PJR van Wyk		CLIENT CONTACT PERSON: Mr Zwakala Zuma		
SYNOPSIS: The report covers the materials investigation, traffic evaluation and pavement design for the two sections of Main Road P419.				
KEY WORDS: P419, Traffic Study, Material Investigation, Pavement Design				
© COPYRIGHT: ILIFA AFRICA ENGINEERS (PTY) LTD				
QUALITY VERIFICATION				SACAS ISO 9001:2015
This report has been prepared under the controls established by a certified ISO 9001:2015 quality management system developed by Ilifa Africa Engineers (Pty) Ltd.				
Verification	Capacity	Name	Signature	Date
By Author	Technologist	P.J.R. van Wyk		2020-07-21
Checked by	Technologist	A.W. Poortman		2020-07-21
Authorized by	CEO	J.J. Olivier		2020-07-21
No. of Copies Made:	Print Date: 2020-07-21	No of Reprints:	Date:	
Copies sent to:			Deliver Method:	
1. Mr Zwakala Zuma			Hard Copy	
2.				
3.				



TABLE OF CONTENTS

1. INTRODUCTION..... 1

1.1. APPOINTMENT 1

1.2. PURPOSE OF REPORT 1

1.3. SCOPE OF CONSTRUCTION WORK 1

2. SITE LOCATION AND DESCRIPTION 3

2.1. SITE LOCALITY 3

2.2. GENERAL DESCRIPTION OF ROAD 4

2.3. CLIMATE 5

3. EXISTING SERVICES 7

4. MATERIALS INVESTIGATION 8

4.1 MATERIALS INVESTIGATION DONE BY VNA CONSULTING 8

4.2 MATERIALS INVESTIGATION DONE BY ILIFA AFRICA ENGINEERS 8

4.3 GENERAL GEOLOGY 9

4.4 TEST PIT DATA 10

4.5 TEST PIT DISCUSSION 14

4.6 DCP TEST RESULTS 15

4.7 TEST PIT AND DCP TEST CONCLUSIOS DATA 17

4.8 BORROW PIT INVESTIGATION 17

4.8.1 BORROW PIT 1 18

4.8.2 BORROW PIT 2 18

4.8.3 BORROW PIT 3 18

5. TRAFFIC ANALYSIS 21

5.1 INFORMATION AND DESIGN GUIDELINES..... 21

5.2 TRAFFIC COMPOSISTION 21

6. PAVEMENT DESIGN..... 24

6.1 PAVEMENT DESIGN..... 24

7. CONSTRUCTION MATERIALS..... 26

7.1 SELECTED SUBGRADE AND SUBBASE LAYERS 26

7.2 CRUSHED STONE BASE 26

7.3 WATER 26

8. STORMWATER DRAINAGE 27

9. CONCLUSIONS AND RECOMMENDATION 28

9.1 CONCLUSIONS 28

9.2 RECOMMENDATION 29

10 APPROVAL 30



LIST OF TABLES

TABLE 2-1: PROJECT SUMMARY

TABLE 2-2: CLIMATIC STATISTICS

TABLE 4-2: TEST PITS SUMMARISED RESULTS VNA MATERIALS INVESTIGATION (KM 4.6 TO KM 10.1)

TABLE 4-3: TEST PITS SUMMARISED RESULTS ILIFA MATERIALS INVESTIGATION (KM 18.85 KM 21.75)

TABLE 4-4: SUMMARY OF DCP RESULTS

TABLE 4-5: BORROW PIT POSITIONS

TABLE 5-1: DESIGN TRAFFIC

TABLE 6-1: PROPOSED PAVEMENT DESIGN

LIST OF FIGURES

FIGURE 2-1: LOCALITY PLAN

FIGURE 2-2: AVERAGE TEMPERATURES AND PRECIPITATION

FIGURE 4-1: TYPICAL SUBSOIL PROFILE IN MUDSTONE AREAS

FIGURE 4-2: COLLUVIAL SOILS UNDERLAIN WITH BEDROCK

FIGURE 4-4: BORROW PIT LOCATIONS

FIGURE 5-1: SENSITIVITY ANALYSIS

ANNEXURES

ANNEXURE A: VNA CONSULTING MATERIAL TEST RESULTS

ANNEXURE B: ILIFA AFRICA MATERIAL TEST RESULTS

ANNEXURE C: BORROW PIT TEST RESULTS

ANNEXURE D: ILISO TRAFFIC STUDY

ANNEXURE E: RESULTS FROM RUBICON DESIGN SOFTWARE



1. INTRODUCTION

1.1. APPOINTMENT

Ilifa Africa Engineers (Pty) Ltd have been appointed for the Underberg Area Offices for a three-year period, in a letter dated 2 November 2017. Since Main Road P419 falls in the same Underberg area, the existing appointment was extended to include the upgrading of this road from gravel to blacktop. Order Number E0060865 was issued on 1 August 2019 by the Department.

Km 0.0 to km 4.4 and Km 22.0 to Km 24.0 have already been upgraded to blacktop by VNA Consulting during previous contracts.

The current appointment of Ilifa Africa entails the detail design, tender documentation, project implementation, full time supervision and close-out of the project. The sections of road that will be upgraded now is Km 4.4 to Km 9.4 and Km 17.0 to Km 22.0

1.2. PURPOSE OF REPORT

The report covers the materials investigation, traffic evaluation and pavement design for the two sections of road. The main purpose of the report is to provide enough details regarding the proposed pavement design for the KZN Department of Transport to issue a pavement Design Certificate (PDC).

1.3. SCOPE OF CONSTRUCTION WORK

The project comprises the construction of two sections of 5 kilometres each, Km 4.4 – Km 9.4 and Km 17.0 - Km 22.0. The scope of works include mass earth works, layer works, asphalt surfacing, concrete side drains, new pipe and box culverts as well as sidewalks, with road signs and road markings. The total proposed surfacing width is 7.0 m and consists of 2 x 3.5m lanes. A 1.5m wide sidewalk will be provided at the following areas:

- Left Hand Side (Increasing chainages):
 - Km 5.237 – km 6.041
 - Km 7.680 – km 9.753
 - Km 20.168 – km 22.120

- Right Hand Side (Increasing chainages):
 - Km 4.513 – km 5.258
 - Km 8.524 – km 8.285
 - Km 16.600 – km 21.120



The detail scope of the works includes the following:

- Establishment on site and clearing and grubbing
- Provision of traffic accommodation facilities
- Survey requirements
- Road layer works
 - Mass earthworks consisting of G10 material compacted to 93% MDD in layers of 150mm, where required
 - Rip and recompact the roadbed and compact the material to 93% MDD
 - 150mm G7 selected layer compacted to 95% MDD
 - 150mm C4 subbase compacted to 96% MDD
 - 150mm G2 crushed stone base compacted to 85% BRD
 - 30mm Medium Continuously Graded Asphalt
- Sidewalk layer works
 - Mass earthworks consisting of G10 material compacted to 93% MDD in layers of 150mm, where required
 - Rip and recompact the roadbed and compact the material to 93% MDD
 - 150mm G6 material compacted to 95% MDD
 - 125mm G5 material compacted to 97% MDD
 - 20mm Fine Graded Asphalt
- Road prism drainage
- Extension of existing culverts
- Construction of erosion protection measures (gabions, stone pitching, etc.)
- Installation of guardrails, where required
- Installation of new road signs
- New road markings and road studs
- Finishing and cleaning up of the road and road reserve
- Continuous quality control over materials and workmanship, and compliance with the Particular Specifications with regards to environmental management and occupational health and safety, during all the above construction activities.
- Removal of all site establishment facilities and constructional plant on completion of the Works



2. SITE LOCATION AND DESCRIPTION

2.1 SITE LOCALITY

Table 2-1 indicates the summary for the road under consideration.

TABLE 2-1: PROJECT SUMMARY

Project Name	Physical Address	District Municipality	Y- Co-ordinate	X- Co-ordinate
Upgrade of Main Road P419 From Km 4.4- Km 9.4 & Km 17.0 – Km 22.0	Main Road P419 From Km 4.4- Km 9.4 & Km 17.0 – Km 22.0. Hlanganani	Harry Gwala District Municipality	29° 45'47.3342"S	29° 51'55.2224"E

The locality map of Main Road P419 as well as the two sections of road under consideration is indicated in **Figure 2-1**.




FIGURE 2-1: LOCALITY PLAN

2.2 GENERAL DESCRIPTION OF ROAD

Road P419 traverses hilly to mountainous terrain in a rural area of KwaZulu-Natal between the R617 (P7-3) and P612 (P23-1), linking Deepdale and Donnybrook. The total length of road P419 is approximately 24.0km.

There are numerous existing culverts crossing the road as well as a portal culvert and a partially completed bridge structure at km 3.5.

The portion of the existing gravel road to be upgraded has a nominal width of 7.5 metres and the overall length is approximately 10.0 km.

Ilifa Africa Engineers has been appointed for the following two sections:

- km 4.4 and continues to km 9.4,
- km 17.0 and continues to km 22.0



The following sections have been upgraded to blacktop under previous contracts:

- km 0.0 – km 4.4
- km 22.0 – km 24.0

2.3 CLIMATE

A summary of the climatic statistics is given in **Table 2-2**. Information obtained from www.timeanddate.com for Ixopo between 2005 and 2015, was used for the summary.

TABLE 2-2: CLIMATIC STATISTICS

Property	Value
Average Annual Maximum Temperature	24.8°C
Average Annual Minimum Temperature	9.6°C
Highest Maximum Temperature	28.0°C
Lowest Minimum Temperature	3.0°C
Average Annual Rainfall	589.6mm
Maximum Monthly Rainfall	103.9mm

This is a high summer rainfall area with an average annual rainfall of 589.6mm. Most rain occurs from October to April. The maximum average daily summer temperature is 26.6°C and the minimum average daily winter temperature is 5.8°C.

The average temperatures and precipitation are shown in **Figure 2-2**.




FIGURE 2-2: AVERAGE TEMPERATURES AND PRECIPITATION



3. EXISTING SERVICES

All known existing services are indicated on the layout drawings. It should be noted that there is an existing main power line that runs adjacent to Main Road P419 from Km 16.8 to about Km 19.4. Furthermore, there is a large water main line (owned by the Harry Gwala District Municipality) that runs parallel to the existing alignment of P419 from Km 18.9 to Km 22.5. Construction in these sections will require extreme caution.

It is also expected that unknown domestic services crossings, requiring relocation or protection, may be encountered along the route as the work proceeds. The Contractor shall make every effort to locate all these services prior to excavations commencing in that area. Such efforts shall include diligent enquiry and discussions with adjacent landowners, visual surface inspection and exploratory trenching investigation, as required.



4. MATERIALS INVESTIGATION

4.1 MATERIALS INVESTIGATION DONE BY VNA CONSULTING

During VNA Consulting's appointment a materials investigation was done by Soilco in July 2011. The materials information was obtained from VNA Consulting's "*Materials Investigation and Utilisation Report for the upgrade of the district road P419 (km0.6 – km10.6)*".

Information from the previous report has been used for the pavement design of the first section of main road P419 (Km 4.6 to Km 10.10). Ilifa Africa has no record of a Pavement Design Certificate (PDC) for the first section of road as done by VNA Consulting.

During the previous materials investigation, a total of twenty test pits were excavated at 500m intervals, alternating between left hand side and right-hand side of the proposed centre line. Twenty-one DCP tests were also done along the road as part of the materials investigation. A summary of the material properties of the original investigation done by Soilco is summarised in **Table 4-2**.

Two borrow pits were also identified during the previous materials investigation, and a total of 5 samples from the exposures, faces and excavation pits of these borrow pits were taken. A third potential borrow pit was later identified along road D2434 and tested.

The locations of the borrow pits can be seen in **Table 4-5 and Figure 4-4**.

4.2 MATERIALS INVESTIGATION DONE BY ILIFA AFRICA ENGINEERS

Subsequently to the previous materials investigation done by Soilco, Ilifa Africa appointed Geosure to conduct the materials investigation for the second road section between Km 16.3 and Km 21.75.

A total of eleven test pits were excavated at 500m intervals, alternating between left hand side and right-hand side of the proposed centre line. Ten DCP tests were also done along the road as part of the materials investigation.

A summary of the material properties done by Geosure is summarised in **Table 4-3**.



4.3 GENERAL GEOLOGY

In general, the following typical subsoil horizons can be found in areas underlain by mudstone:

- Dry to slightly moist, dark brown, firm, intact, slightly clayey sandy silt – Colluvium. The colluvial soils extend to an average depth of 0,7 metres below existing ground level.
- Slightly moist, deep pinkish red to red and yellowish brown, soft to firm, intact moderately clayey silt – Residual Mudstone. The residual soils extend to bedrock level at an average depth of 1,2 metres below existing ground level.
- Dark pink/reddish pink to yellow and yellowish brown, completely to highly weathered, very fine to fine grained, thinly laminated, highly fractured, extremely soft to very soft rock – Mudstone.
- In some instances, the residual soils are completely absent and colluvial soils (generally less than 0,5 metres thick) are underlain directly by mudstone bedrock.

The geology of the greater Underberg Area is characterised by mudstone and sandstone bedrock of the Adelaide Formation, which is in turn intruded extensively by younger Jurassic age dolerite.

Figure 4-1 and **Figure 4-2** provide typical examples of the soil profile on Main Road P419.



FIGURE 4-1: TYPICAL SUBSOIL PROFILE IN MUDSTONE AREAS



FIGURE 4-2: COLLUVIAL SOILS UNDERLAIN WITH BEDROCK

4.4 TEST PITS DATA

The material test results for the materials investigation done by VNA Consulting are attached in **Annexure A** and the materials investigation done by Ilifa Africa are attached in **Annexure B**.



As indicated above, samples of the test pit layers were taken to determine the grading, Atterberg limits, CBR values and COLTO classification. A summary of the material properties done by Soilco is summarised in **Table 4-2**. A summary of the material properties done by Geosure is summarised in **Table 4-3**.



MAIN ROAD P419 KM 4.40 - KM 9.40 & KM 17.0 - KM 22.0

TABLE 4-2: TEST PITS SUMMARISED RESULTS VNA MATERIALS INVESTIGATION (KM 4.6 TO KM 10.1)

DISTANCE (KM)	TEST PIT NUMBER	DEPTH	SAMPLE DATA											SUMMARY OF TEST RESULTS													COLTO CLASSIFICATION
			SIEVE ANALYSIS (% PASSING)											ANALYSIS							CBR						
			75.0	63.0	59.0	37.6	26.5	19.0	13.2	4.75	2.0	0.425	0.075	GM	LL	PI	LS	OMC	MDD	MC	SWELL	100%	98%	95%	93%	90%	
4+600 LHS	TP9	0-500	78	78	78	78	77	71	64	49	42	33	21	2.4	24	8	4.1	9.2	2044	9.3	0.91	30	23	15	11	7	G8
	TP9	500-600								100	99	92	83	0.26	47	11	6.0										NA
	TP9	600-900						100	97	74	62	48	28	1.62	25	8	4.5	10.3	2006	10.2	0.97	29	24	17	14	11	G8
5+100 RHS	TP10	0-350		100	87	81	77	74	68	50	38	26	16	2.20	24	8	4.0	9.9	2070	9.9	0.16	98	78	55	39	21	G5
	TP10	350-1000								100	99	62	31	1.07	30	7	3.5	14.0	1882	14.3	0.95	41	36	30	23	16	G7
5+600 RHS	TP11	30-1000								100	98	55	26	1.21	29	6	3.0	14.3	1842	14.3	0.87	36	32	26	21	15	G8
6+100 RHS	TP12	0-500						100	95	82	73	52	26	1.49	26	10	5.0	9.7	2036	9.7	0.91	40	30	20	14	9	G8
6+600 LHS	TP13	0-200						100	92	76	64	45	23	1.68	24	8	4.0	9.2	2083	9.2	0.28	58	50	39	26	14	G6
	TP13	200-1000						100	99	98	91	75	0.36	28	11	5.5	13.8	1810	13.7	2.52	18	11	6	3	2	NA	
7+100 RHS	TP14	0-1000						100	98	92	85	78	0.46	42	20	10.0	17.9	1702	17.7	1.93	24	20	13	9	5	G9	
7+600 LHS	TP15	0-60			100	93	93	67	60	46	38	27	17	2.17	26	10	5.0										NA
	TP15	60-250						100	99	97	94	88	77	0.41	34	15	7.5	100	99	97							NA
	TP15	250-1000								100	99	99	93	0.09	46	17	8.5	18.8	1691	18.6	5.15	7	6	4	4	4	NA
8+100 RHS	TP16	0-600						100	98	79	68	53	35	1.44	24	8	4.0	9.2	2043	9.1	2.13	25	22	17	12	7	G8
	TP16	600-1000						100	99	94	89	77	59	0.76	25	12	6.0	12.2	1901	12.2	161	20	13	7	5	3	G10
8+600 LHS	TP17	0-800					100	98	91	49	32	15	8	2.45	25	10	5.0	9.6	1992	9.6	1.08	56	40	24	18	12	G7
9+100 RHS	TP18	0-850	80	80	70	70	69	68	60	50	45	35	20	2.01	27	10	5.0	10.2	2063	10.2	0.84	48	37	25	17	9	G7
	TP18	850-900			100	95	91	87	81	66	59	47	39	1.56	27	11	5.5										NA
9+600 LHS	TP19	0-300						100	99	90	68	35	18	1.78	25	11	5.5	8.8	2121	8.7	0.23	28	25	16	11	7	G8
10+100 RHS	TP20	0-300						100	98	93	93	88	0.21	49	21	10.5	19.4	1664	19.3	1.65	18	12	7	4	2	NA	



MAIN ROAD P419 KM 4.40 - KM 9.40 & KM 17.0 - KM 22.0

TABLE 4-3: TEST PITS SUMMARISED RESULTS ILIFA MATERIALS INVESTIGATION (KM 18.85 KM 21.75)

DISTANCE (KM)	TEST PIT NUMBER	DEPTH	SAMPLE DATA																SUMMARY OF TEST RESULTS										COLTO CLASSIFICATION		
			SIEVE ANALYSIS (% PASSING)																ANALYSIS					CBR							
			75.0	63.0	53.0	50.0	37.5	28.0	26.5	20.0	19.0	14.0	13.2	5.0	4.75	2.0	0.425	0.075	GM	LL	PI	LS	OMC	MDD	SWELL	100%	98%	95%		93%	90%
16+300	IP10	10-200		100	97	95	93	85	85	80	80	71	71	51	51	37	24	19	2.20	28	8	6.5	6.7	2146	1.0	93.0	51.0	21.0	12.0	4.7	G10
	IP10	200-1500				100	99	98	98	98	98	97	97	95	95	90	70	67	0.73	51	16	12.0	19.1	1669	0.3	53.0	35.0	19.0	13.0	6.8	G10
16+700	IP9	10-700	96	96	86	85	83	78	78	72	72	63	63	45	45	39	31	21	2.1	28	9	4.5	8.7	2122	0.7	59.0	42.0	26.0	19.0	11.0	G6
	IP9	700-1500										100	99	99	94	94	86	68	0.80	48	15	10.5	18.3	1638	0.3	45.0	30.0	16.0	11.0	5.8	NA
18+250	IP8	10-250	97	97	87	86	84	78	78	73	73	63	63	45	45	39	30	21	2.1	27	7	6	8.7	2106	0.6	99.0	50.0	18.0	8.9	3.2	G9
	IP8	250-1500											100	99	99	90	78	68	0.64	46	15	10.5	17.1	1692	0.1	11.0	10.0	9.5	9.0	8.3	NA
18+750	IP7	10-200		100	96	96	90	88	88	84	84	77	77	60	60	47	32	21	2.01	25	7	5.5	5.7	2235	0.4	62.0	34.0	14.0	7.6	3.1	G10
	IP7	200-1150				100	96	94	94	88	88	85	85	77	77	70	62	51	1.17	40	12	9.5	15.5	1741	1.0	27.0	22.0	16.0	13.0	9.5	G9
18+850	IP11	10-100		100	99	97	96	94	94	91	91	79	79	57	57	44	30	20	2.05	27	9	6	6.1	2202	0.3	107.0	66.0	32.0	20.0	9.4	G7
	IP11	100-1400										100	99	99	97	97	91	86	0.41	49	16	12	12.0	1724	0.5	26.0	20.0	14.0	10.0	7.0	G9
19+250	IP6	200-1000	100	97	96	96	94	93	93	93	93	92	92	89	89	84	73	61	0.82	54	19	11.0	22.0	1627	0.7	24.0	14.0	6.7	4.0	1.9	>G10
19+750	IP5	10-200	92	91	90	90	89	84	84	79	79	70	70	53	53	44	33	25	1.99	29	8	5.0	7.3	2163	0.2	85.0	48.0	21.0	12.0	5.0	G8
	IP5	200-500	100	97	94	93	91	87	87	85	85	80	80	68	68	59	46	34	1.61	34	9	6.5	13.0	1872	0.5	22.0	15.0	8.5	5.9	3.3	G10
	IP5	500-1500								100	99	99	98	98	95	95	85	75	0.95	43	14	8.5	12.2	1701	2.4	28.0	18.0	9.4	6.0	3.1	NA
20+250	IP4	10-200		100	94	94	88	82	82	76	76	64	64	38	38	31	25	20	2.24	27	8	7.0	7.8	2101	0.7	116.0	71.0	34.0	21.0	10.0	G7
	IP4	200-540				100	99	99	99	98	98	98	98	93	93	78	62	56	1.05	44	12	9.0	18.9	1593	1.8	19.0	15.0	11.0	8.6	6.2	>G10
	IP4	540-1400				100	99	99	99	99	99	95	95	82	82	71	63	58	1.07	40	11	8.5	13.8	1749	0.8	10.0	9.9	9.4	9.2	8.8	G9
20+750	IP3	100-600				100	99	99	99	98	98	97	97	94	94	79	63	58	1.00	43	16	9.0	19.2	1589	1.9	14.0	9.9	6.0	4.3	2.6	>G10
	IP3	600-1500	88	83	75	75	70	68	68	64	64	53	53	35	35	28	24	22	2.25	34	10	7.0	11.9	1945	0.2	19.0	16.0	13.0	11.0	8.5	G8
21+250	IP2	10-200	96	96	88	87	81	78	78	73	73	70	70	56	56	49	41	29	1.81	26	8	5.0	9.0	2051	1.1	43.0	20.0	6.0	2.7	0.8	>G10
	IP2	200-500		100	96	96	96	93	93	93	93	91	91	87	87	85	82	77	0.56	36	12	7.5	15.5	1803	2.9	6.1	5.6	4.9	4.5	4.0	>G10
	IP2	500-930														100	99	93	0.08	41	12	7.0	17.6	1771	2.7	7.8	5.1	2.7	1.8	0.9	>G10
21+750	IP1	10-200	98	98	95	95	93	87	87	80	80	70	70	53	53	46	38	28	1.88	27	6	4.5	8.2	2090	0.2	44.0	32.0	19.0	14.0	8.1	G8
	IP1	200-800											100	98	98	89	81	73	0.57	40	13	10.5	15.1	1710	0.1	17.0	13.0	9.0	6.9	4.7	NA
	IP1	800-1500												100	99	96	53	0.52	35	11	8.0	15.3	1762	0.6	35.0	23.0	12.0	7.9	4.2	NA	



4.5 Test Pit Discussion

Materials Investigation Done by VNA Consulting

The following two horizons were derived from the test pit results.

- The first horizon had an average depth of 300mm with a COLTO classification between G5 and G8. Three (3) tests did not obtain any COLTO classification. The CBR values ranged between 4.0 – 55.0 at 95% MOD AASHTO Density.
- The second horizon had an average depth of 500mm with a COLTO classification between G7 and G10. Four (4) tests did not obtain any COLTO classification. The CBR ranged between 4.0 – 30.0 at 95% MOD AASHTO Density.

The material that could not be classified was mostly as a result of very low Grading Moduli. From the results above it is evident that that the material varies substantially along the road.

Materials Investigation Done by Ilifa Africa Engineers

The following three horizons were derived from the test pit results.

- The first horizon had an average depth of 300mm with a COLTO classification between G6 and bigger than G10. The CBR ranged between 6.0 – 34.0 at 95% MOD AASHTO Density.
- The second horizon had an average depth of 600mm with a COLTO classification between G7 and G10. Four (4) tests did not obtain any COLTO classification. The CBR ranged between 9.0 – 19.0 at 95% MOD AASHTO Density.
- A third horizon had only been encountered between km 19+750 to km 21+750. The average depth was 800mm with a COLTO classification between G9 and bigger than G10. Two (2) sections, km 19.750 and km 21+750, did not obtain any COLTO classification. The CBR ranged between 2.7 – 12.0 at 95% MOD AASHTO Density.

The material that could not be classified was mostly as a result of very low Grading Moduli. From the results above it is evident that that the material varies substantially along the road.

The existing material to a depth of approximately 300mm (for both sections of road) can be used for mass earthworks and selected material. Any in-situ material not obtaining a COLTO classification, will have to be removed, spoiled, and replaced with G10 material.



4.6 DCP Test Results

DCP Test Done by VNA Consulting

Table 4-4 indicates a summary of the DCP test results conducted by VNA Consulting for the depths of the horizons as per the test pits

TABLE 4-4: SUMMARY OF DCP RESULTS: VNA CONSULTING

POSITION (KM)	CBR @ 0.3M	CBR @ 0.8M	POSITION (KM)	CBR @ 0.3M	CBR @ 0.8M
4+600	Refusal	Refusal	7+400	40	39
4+800	Refusal	Refusal	7+600	30	28
5+000	50	37	7+800	70	Refusal
5+200	50	30	8+000	70	Refusal
5+400	Refusal	Refusal	8+400	30	Refusal
5+600	55	47	8+600	45	Refusal
5+800	Refusal	Refusal	8+800	75	Refusal
6+000	Refusal	Refusal	9+000	45	39
6+200	Refusal	Refusal	9+200	Refusal	Refusal
6+400	30	50	9+400	Refusal	Refusal
6+600	30	38	9+600	75	Refusal
6+800	75	Refusal	9+800	50	Refusal
7+000	22	45	10+000	60	Refusal
7+200	8	35			

Refusal was encountered on 8 of the DCP tests at a depth of 300mm, while refusal at a depth of 800mm were encountered 17 times.

The CBR value at a depth of 300mm varies between 8 and 75 with an average of CBR of 48.

The CBR value at a depth of 800mm varies between 28 and 50 with an average of CBR of 39.

The DCP refusals may be the result of a very dense layer of rocks. It can be assumed that since the existing road was constructed on the ridge lines, the refusal is due to scattered rocks in the underlying layers.



DCP Test Done by Ilifa Africa Engineers

Table 4-5 indicates a summary of the DCP test results conducted by Ilifa Africa Engineers for the depths of the horizons as per the test pits.

TABLE 4-5: SUMMARY OF DCP RESULTS: ILIFA AFRICA ENGINEERS

POSITION (KM)	CBR @ 0.3M	CBR @ 0.6M
16+300	15	10
16+700	15	10
18+250	14	7
18+750	21	19
18+850	10	14
19+250	17	14
19+750	25	27
20+250	27	21
20+750	19	21
21+250	12	8

The CBR value at a depth of 300mm varies between 14 and 27 with an average of CBR of 18.

The CBR value at a depth of 600mm varies between 7 and 27 with an average of CBR of 15.

No refusal was encountered on any of the DCP tests.



4.7 Test Pits and DCP Conclusions

According to the test pit and DCP tests results, it can be concluded that the in-situ material is of poor quality and only the classified materials can be used as earth works.

The average CBR for the test pits and the DCP tests are similar for each horizon.

The TRH4 states that the CBR of the in-situ subgrade material must be higher than 15, to provide proper bearing capacity. Where the sub grade strength (CBR) is below 15, material of a better quality will have to be imported. This will only be done at certain areas of the road.

According to test pit results and DCP tests, the material for both sections, km 4.40 to km 9.4 and km 17.0 to km 22.0, are of similar nature.

4.8 Borrow Pit Investigation

During the initial materials investigation done by Soilco, three borrow pits have been identified close to Main Road P419. The coordinates of the borrow pits are provided in **Table 4-5** and the positions indicated on the aerial map in **Figure 4-4**.

TABLE 4-5: BORROW PIT POSITIONS

Location of Possible Borrow Pit Sites			
Borrow Pit No.	Road Name	Latitude	Longitude
1	D2423	29° 47' 55.21"	29° 52' 36.32"
2	D1208	29° 50' 35.7"	29° 52' 09.9"
3	P419	29° 47' 54.1"	29° 52' 33.0"




FIGURE 4-4: BORROW PIT LOCATIONS

Details of the borrow pits are described in the following paragraphs.

4.8.1 Borrow Pit 1

The material identified in this borrow pit consists of a very hard to hard Dolerite rock. This borrow pit is situated adjacent to road D2423 approximately 4.5km from Main road P419. The volume of material in this borrow pit would easily provide sufficient materials for both the base and sub-base layers.

The volume of the borrow pit is approximately 27000m³ with a depth of 4.0 to 6.0metres. Several scattered boulders were visible indicating signs of previous mining.



The material from this borrow pit was not tested or classified. From the visual appearance, the material appears to be between G5 and G6 quality. If this material is crushed and broken down sufficiently it should be possible to stabilize the material to at least C4 stabilized layer. The overburden material recovered from the bulk excavation process of this borrow pit can be utilised in the lower pavement layers. This potential hard rock borrow pit would only be considered as a last option, as the site is approximately 4.5 kilometres from Main Road P419. In needed, the material will be tested to confirm the assumed properties

4.8.2 Borrow Pit 2

This borrow pit is situated adjacent to road D1208 which intersects Main Road P419 at km 7.4. The material identified in borrow pit 2 consists predominately of hard to medium dense weathered Shale. This borrow pit appears to have been mined by the Department of Transport for the re-graveling activities of the roads in the close vicinity. The volume of the borrow pit is approximately 10000m³ with a depth of 2.0 to 4.0metres.

The material of this borrow pit was sampled and tested by *Soilco Materials Investigations* during their material investigation of the road centre line. The borrow pit has good quality material conforming to G5 and G7 standards.

If material from this borrow pit can be used for the layer works, it would contribute to a saving of the hauling cost of importing commercial material. There is sufficient material in the borrow pit to provide at least 50% of the material for the base and sub-base

4.8.3 Borrow Pit 3

Borrow pit 3 is situated along Main Road P419 at km 12.5. The material identified in borrow pit 3 consisted predominately of hard to medium dense Dolerite rock and weathered Shale. This borrow pit appears to have been rehabilitated from previous use. This material was probably mined by Department of Transport for the re-graveling activities of the roads in the close vicinity.

The material was sampled and tested by *Soilco Materials Investigations* during their materials investigation of the road centre line. The quality of material conforms to G5 and G7 quality.

The volume of material in the borrow pit is estimated at approximately 18000m³ with a depth of about 4.0m. This borrow pit is located approximately 4.0 kilometres from the start of the project on the Polela side and ideally situated to limit the cost of moving the material.



This borrow pit site has a good open area for stockpiling operations during construction, which would aid the contractor in materials selection. The overburden material that will be recovered from the bulk excavations can be used for the fill or lower pavement layers.

During construction, it is envisaged to make use of a mobile laboratory or alternatively a commercial laboratory to manage the quality control of materials leaving the borrow pit as well as classifying various faces of the borrow pit. An environmental officer will also be appointed to the project to ensure the contractor complies with all environmental laws surrounding the sourcing of natural material for road construction.

The laboratory results are attached hereto as **Annexure C**.



5. TRAFFIC ANALYSIS

5.1 INFORMATION AND DESIGN GUIDELINES:

The following design guidelines were utilized to calculate the design traffic and to determine the pavement design:

- Human Settlement Planning and Design : Guidelines (Red book)
- TRH4 : Structural design of inter urban and rural roads
- TRH17 : Geometric Design of Rural Roads
- TRH13 : Cementitious Stabilizers in Road Construction
- COLTO : Standard Specifications for Road and Bridge Works for State Road Authorities (1998 edition)

5.2 TRAFFIC COMPOSITION:

A complete Traffic Impact Assessment was conducted by Iliso Consulting in May 2012. **Table 5-1** indicates the estimated design traffic:

TABLE 5-1: DESIGN TRAFFIC (2012)

ADT PER LANE	% HEAVIES	ADTT	80 KN EQUIVALENT STANDARD AXLES		TOTAL PRESENT 80 KN EQUIV. STANDARD AXLES/DAY
			LIGHTS	HEAVIES	
343	3.2%	11	0.91	36.3	37.21

The above-mentioned figures were first extrapolated to 2022 values (time of opening the road), using a growth rate of 4%, after this a growth rate of 6% was applied to determine the final traffic volumes for the pavement design. The growth rates applied, are as per the TRH 4. If a value of 54 E80's per day and a design life of 20 years are assumed, the total design E80's for this section of road is 0.765 million (ES 1).

**TABLE 5-2: DESIGN LOADING SECTION**

PARAMETER	VALUE
HEAVIES/LANE/DAY	11
E80/HEAVY (BASED ON HEAVY VEHICLE SPLIT)	1.5*
E80/LANE/DAY	54
PAVEMENT STRATEGY 1: RESTORATION	
DESIGN LIFE	20
DESIGN E80/LANE/DAY	54
DESIGN E80'S FOR LIFE	0.765
PAVEMENT CLASS	ES1

*The average E80's per heavy vehicle was determined by the weighted average of the split between long, medium and short heavy vehicles and the E80's for each type. The split and E80's per heavy vehicle can be seen in **Figure 5-1**.

In **Figure 5-1** a sensitivity analysis was carried out to determine the effect of various growth rates on the pavement classification. For typical growth rates varying between 4%-6%, the traffic classification remains as an ES 1 and therefore the growth rate is not sensitive to the design E80's.

The Traffic Impact Assessment done by Iliso Consulting is attached hereto as **Annexure D**.



MAIN ROAD P419 KM 4.40 - KM 9.40 & KM 17.0 - KM 22.0

TRAFFIC PROJECTIONS

CLIENT: DEPARTMENT OF TRANSPORT: KWAZULU NATAL
 PROJECT: THE UPGRADING OF ROAD P419 FROM GRAVEL TO BLACKTOP
 DATE: 03 May 2019

TRAFFIC COUNTS IN WORST LANE

CLASS (ave E80's)	Light Vehicles	Busses (1.03)	2-Axles (1.08)	3-Axles (2.51)	4-Axles (2.66)	5-Axles (3.25)	6-Axles (5.17)	7-Axles (6.51)
COUNTS	332		0		0	11	0	

INITIAL AADT/LANE: 343 HEAVIES: 3.2% INITIAL AADTT/LANE: 11

AVE AXLES/HEAVY VEHICLE: 4 INITIAL HEAVY AXLES/LANE/DAY: 44

HEAVY AXLE DISTRIBUTION

CATEGORY (KN)	20-40	40-60	60-80	80-100	100-120	120-140
% - AXLES (TOTAL 100%)	0%	0%	0%	0%	0%	0%
NUMBER OF AXLES	0	0	0	0	0	0

OR AVE E80 AXLES/HEAVY VEHICLE: 3.3

n VALUE (4.2): 4.2 INITIAL E80 AXLES/LANE/DAY: 36 AXLE LOAD FACTOR (P): 0.83

DATE OF COUNTS: 2012 DATE OF CONSTRUCTION: 2022 DESIGN LIFE: 20

GROWTH RATE TO CONST: 4% YEARS: 10 DESIGN E80 AXLES/LANE/DAY: 54

GROWTH RATE 1: 0% YEARS: 0
 GROWTH RATE 2: 6% YEARS: 20 DESIGN E 80's FOR LIFE: 0,765 mil

SENSITIVITY (AXLE LOAD FACTOR VARIES BETWEEN 0.2 AND 0.8)

GROWTH RATE VARIES BETWEEN 4% AND 10%

E80 GROWTH	AXLE LOAD FACTOR	E 80- REPETITIONS (millions) over various design life's with different axle load factors & traffic growth rates (Years)												
		2	4	5	6	8	10	12	14	15	16	18	20	25
4,00%	0.2	0,0100	0,0209	0,0266	0,0326	0,0453	0,0590	0,0739	0,0899	0,0984	0,1073	0,1260	0,1464	0,2047
	0.4	0,0201	0,0417	0,0532	0,0652	0,0906	0,1180	0,1477	0,1798	0,1968	0,2145	0,2521	0,2927	0,4094
	0.6	0,0301	0,0626	0,0799	0,0978	0,1359	0,1770	0,2216	0,2697	0,2952	0,3218	0,3781	0,4391	0,6141
	0.8	0,0401	0,0835	0,1065	0,1304	0,1811	0,2360	0,2954	0,3596	0,3937	0,4291	0,5042	0,5854	0,8187
5,50%	0.2	0,0102	0,0216	0,0278	0,0343	0,0485	0,0642	0,0817	0,1012	0,1117	0,1229	0,1470	0,1738	0,2550
	0.4	0,0205	0,0433	0,0557	0,0687	0,0969	0,1284	0,1634	0,2024	0,2235	0,2457	0,2940	0,3477	0,5101
	0.6	0,0307	0,0649	0,0835	0,1030	0,1454	0,1926	0,2451	0,3035	0,3352	0,3686	0,4410	0,5215	0,7651
	0.8	0,0410	0,0866	0,1113	0,1374	0,1939	0,2568	0,3268	0,4047	0,4469	0,4914	0,5880	0,6954	1,0202
7,00%	0.2	0,0105	0,0225	0,0291	0,0362	0,0519	0,0699	0,0905	0,1140	0,1271	0,1410	0,1719	0,2073	0,3198
	0.4	0,0209	0,0449	0,0582	0,0723	0,1038	0,1397	0,1809	0,2281	0,2541	0,2820	0,3438	0,4146	0,6397
	0.6	0,0314	0,0674	0,0872	0,1085	0,1556	0,2096	0,2714	0,3421	0,3812	0,4231	0,5158	0,6219	0,9595
	0.8	0,0419	0,0898	0,1163	0,1447	0,2075	0,2795	0,3618	0,4561	0,5083	0,5641	0,6877	0,8292	1,2793
8,50%	0.2	0,0107	0,0233	0,0304	0,0381	0,0555	0,0761	0,1002	0,1287	0,1448	0,1622	0,2016	0,2481	0,4034
	0.4	0,0214	0,0466	0,0608	0,0762	0,1111	0,1521	0,2005	0,2574	0,2895	0,3244	0,4033	0,4961	0,8068
	0.6	0,0321	0,0698	0,0911	0,1143	0,1666	0,2282	0,3007	0,3861	0,4343	0,4866	0,6049	0,7442	1,2101
	0.8	0,0428	0,0931	0,1215	0,1524	0,2221	0,3043	0,4010	0,5148	0,5791	0,6488	0,8065	0,9922	1,6135
10,00%	0.2	0,0109	0,0241	0,0317	0,0401	0,0594	0,0829	0,1112	0,1454	0,1652	0,1869	0,2370	0,2977	0,5113
	0.4	0,0218	0,0483	0,0635	0,0802	0,1189	0,1657	0,2223	0,2909	0,3303	0,3738	0,4741	0,5955	1,0225
	0.6	0,0328	0,0724	0,0952	0,1203	0,1783	0,2486	0,3335	0,4363	0,4955	0,5607	0,7111	0,8932	1,5338
	0.8	0,0437	0,0965	0,1269	0,1604	0,2378	0,3314	0,4447	0,5817	0,6607	0,7475	0,9482	1,1910	2,0450



SENSITIVITY ANALYSIS




FIGURE 5-1: SENSITIVITY ANALYSIS



6. PAVEMENT DESIGN

6.1 PAVEMENT DESIGN

The pavement design was based on the TRH 4 document for a Category C road and a wet region, and ES1 design traffic loading **Table 6-1** indicates the proposed layer works based on TRH4. Since the materials of both sections of road are of similar nature, one pavement design will be considered.

TABLE 6-1: PROPOSED PAVEMENT DESIGN

SUBGRADE	ROADBED	FILL	SELECTED	SUBBASE	BASE	WEARING
Semi infinite E = 40MPa	Rip and recompact the roadbed compacted to 93% MDD	Mass earthworks consisting of G10 material compacted to 93% MDD in layers of 150mm, where required	150mm G7 upper selected layer compacted to 95% MDD	150mm C4 material compacted to 96% MDD	150mm G2 Crushed stone base compacted to 85% BRD	30mm Medium Continuously Graded Asphalt

The total required material depth for a category C road is 800mm. Based on the layer thicknesses indicated above, the following additional earthworks will therefore be required in areas of fill.

- G10 material compacted to 93% MDD.
- The subgrade must conform to G10 material.

The above pavement layers were analysed using the Rubicon Mechanistic Pavement Design Software which takes into account the increased tyre pressures of 750kPa that was introduced after the TRH4 has been published. The TRH4 is based on tyre pressures of 520kPa. The two methods gave similar design traffic. According to the TRH 4, the G2 layer must be 125mm thick. After the Rubicon Design Software analysis, the thickness of the G2 layer was changed to 150mm due to the increase in tyre pressure and to get a longer design life.



Rubicon Design Software gave a design life of 22.75 years for 700 000 E80's. The results from Rubicon Design Software is attached hereto as **Annexure E**.

Since the two short surfaced sections of Main Road P419 upgraded earlier have an asphalt overlay, it was requested by the Client that the two new sections of P419 should also be surfaced with Asphalt. If there are budgetary constraints a double seal can be considered.

There are new sidewalks planned next to the road at several sections. The proposed layer works for the sidewalk are as follows:

- 20mm Medium Continuously Graded Asphalt
- 125mm G5 material compacted to 97% MDD
- 150mm G6 material compacted to 95% MDD
- Rip and recompact the roadbed compacted to 93% MDD
- Mass earthworks consisting of G10 material compacted to 93% MDD in layers of 150mm, where required



7. CONSTRUCTION MATERIALS

The required construction materials are discussed under the following headings.

7.1 SELECTED SUBGRADE AND SUBBASE LAYERS

The material for the selected subgrade and subbase layers will be obtained from the borrow pits along Main Road P419.

Alternative sources can be investigated by the appointed contractor.

The appointed contractor is required to submit all test results to the engineer for approval before any material is delivered to site.

7.2 CRUSHED STONE BASE

The G2 crushed stone base required for the construction of the base shall be obtained from commercial sources.

The appointed contractor is required to submit all test results to the engineer for approval before any material is delivered to site.

7.3 WATER

No specific source of water for construction purposes was identified. The Contractor will have to make his own arrangements in this regard. Water may be available from local rivers and streams, but the Contractor will have to apply for the required permit for the abstraction from natural sources as well as for the necessary testing to prove its suitability.



8. STORM WATER DRAINAGE

The storm water will be directed to both sides of the road into concrete or earth channels, after which it will be channelled to the low points and released into the existing or new storm water drainage system and natural vegetation.

Several existing culverts will be extended, and several new pipe and box culverts will be constructed, as part of the project. The new bridge over the Luhane River was only partially constructed when the contract was terminated. This bridge will also be completed now under a separate contract



9. CONCLUSIONS AND RECOMMENDATION

9.1 CONCLUSIONS

The following conclusions can be made from the report:

- In general, the in-situ material is of poor quality and only certain sections of the in-situ material can be used for layer works.
- The proposed pavement design for the two sections of road, Km 4.4 to Km 9.4 and Km 17.0 to Km 22.0, is as follows:
 - Mass earthworks consisting of G10 material compacted to 93% MDD in layers of 150mm, where required.
 - Rip and recompact the roadbed and compact the material to 93% MDD
 - 150mm G7 selected layer compacted to 95% MDD
 - 150mm C4 subbase compacted to 96% MDD
 - 150mm G2 crushed stone base compacted to 85% BRD
 - 30mm Medium Continuously Graded Asphalt
- The proposed layer works for the sidewalk is:
 - Mass earthworks consisting of G10 material compacted to 93% MDD in layers of 150mm, where required
 - Rip and recompact the roadbed and compact the material to 93% MDD
 - 150mm G6 material compacted to 95% MDD
 - 125mm G5 material compacted to 97% MDD
 - 20mm Fine Graded Asphalt
- The upgrading of Main Road P419, Km 4.4 to Km 9.4 and Km 17.0 to Km 22.0 will benefit the community and create a substantial number of local jobs.
- The upgrading of the road will also provide much needed training and upliftment of local SMME's.



9.2 RECOMMENDATIONS

It is recommended that:

- The report be reviewed and approved by the Department of Transport.
- The proposed pavement design for the be approved and a Pavement Design Certificate be issued for the project



10. APPROVAL

Xolani Ngcobo

DATE

Support: supported / not supported / as amended

Remarks:

Craig Dewar:

DATE

Approval: approved / not approved / as amended

Remarks:

REPORT APPROVED BY:

J J OLIVIER (Pr. Eng)



MAIN ROAD P419 KM 4.40 - KM 9.40 & KM 17.0 - KM 22.0

ANNEXURE A: VNA CONSULTING MATERIAL TEST RESULTS



MAIN ROAD P419 KM 4.40 - KM 9.40 & KM 17.0 - KM 22.0

ANNEXURE B: ILIFA AFRICA MATERIAL TEST RESULTS



MAIN ROAD P419 KM 4.40 - KM 9.40 & KM 17.0 - KM 22.0

ANNEXURE C: BORROW PIT TEST RESULTS



MAIN ROAD P419 KM 4.40 - KM 9.40 & KM 17.0 - KM 22.0

ANNEXURE D: ILISO TRAFFIC STUDY



MAIN ROAD P419 KM 4.40 - KM 9.40 & KM 17.0 - KM 22.0

ANNEXURE E: RESULTS FROM RUBICON DESIGN SOFTWARE